


QUANTITY SURVEY AND ESTIMATING SUMMARY

PROJECT Wetherbee Elementary/Middle School
CONSTRUCTION MANAGER Tishman Construction Co.
OWNER City of Lawrence
ARCHITECT The Design Partnership of Cambridge
CONTRACTOR EASTERN CONTRACTORS, INC.
DATE 10 July, 2002 (Revised) 23 August, 2002 (Revised)
SUBJECT Excess Ledge Removal Building "A"
C.O.P. # 56 (Revised)
SHEET # 2
TIME EXTENSION 60 DAYS



| | | | |
|-------------------------|-----------|-------|-----------|
| S&R Constr. Inc. (OPEN) | 2531.6 cy | 38.50 | 97,466.60 |
| | 1 | | 0.00 |
| | 1 ls | | 0.00 |
| | 1 ls | | 0.00 |
| | 1 ls | | 0.00 |
| | 1 ls | | 0.00 |

| | | | |
|-------|--|--|-----------|
| TOTAL | | | 97,466.60 |
|-------|--|--|-----------|

401-831-6337 • 401-831-6338

Nº 371

[Quantity Verification Only] JOB INVOICE

JOB INVOICE

S & R CONSTRUCTION CO., INC.

60 DYERVILLE AVENUE
JOHNSTON, R.I. 02919
401-831-6337 • 401-831-6338

No 372

| |
|--------------------------------------|
| TO <i>Eastern Const. Co.</i> |
| ADDRESS |
| <i>Wetherbee School, Lawrence MA</i> |
| ATTENTION |

| | |
|---|-------------------------------------|
| DATE ORDERED <i>5-13-02</i> | ORDER TAKEN BY <i>R. FERRARA</i> |
| PHONE NO. <i>401-855-8716</i> | CUSTOMER ORDER NO. |
| JOB LOCATION <i>Wetherbee School Lawrence MA</i> | STARTING DATE <i>5-13-02</i> |
| JOB PHONE | |
| TERMS | |

| QTY. | MATERIAL | UNIT | AMOUNT |
|------------|--|----------|----------------------|
| | <i>Standard existing brick wall:</i> | | |
| | <i>6' X 4' X 6'</i> | <i>=</i> | <i>5.33 yds.</i> |
| <i>1st</i> | <i>54.5 = 19' X 4.5' X 6'</i> | <i>=</i> | <i>19 "</i> |
| <i>2nd</i> | <i>52.5 = 16' X 6.5' X 6'</i> | <i>=</i> | <i>23.11 "</i> |
| <i>3rd</i> | <i>50.5 = 18' X 8.5' X 6'</i> | <i>=</i> | <i>34 "</i> |
| <i>4th</i> | <i>48.5 = 19' X 8.5' X 6'</i> | <i>=</i> | <i>35.89 "</i> |
| | <i>D LINE = 22' X 11' X 2.5'</i> | <i>=</i> | <i>22.4 "</i> |
| | <i>22 LINE = 12' X 12' X 4.5'</i> | <i>=</i> | <i>22 "</i> |
| <i>*</i> | <i>22 LINE OF F. L. (TRENCH LINE)</i> | | |
| | <i>12' X 12' X 7'</i> | <i>=</i> | <i>37.33 "</i> |
| | <i>D LINE = 60' X 10' X .50'</i> | <i>=</i> | <i>11.11 "</i> |
| | <i>D LINE & 14 LINE = 12' X 18' X 3'</i> | <i>=</i> | <i>24 "</i> |
| | <i>14 LINE 2nd step = 8' X 12' X 2.5'</i> | <i>=</i> | <i>8.9 "</i> |
| | <i>M LINE, Standard column line 12</i> | | |
| | <i>Column line 2 - 2nd step:</i> | | |
| | <i>6.5' X 32' X 10.5'</i> | <i>=</i> | <i>808.88 "</i> |
| | <i>M line Standard column line 12 &</i> | | |
| | <i>Column line 21 = 77' X 48' X 10.5'</i> | <i>=</i> | <i>1,437.33 "</i> |
| | <i>6-10-02 = TOTAL TO DATE</i> | <i>=</i> | <i>2,489.28 yds.</i> |

DESCRIPTION OF WORK

*LEDGE REMOVAL IN
BLDG. = SECTION "A"*

MISCELLANEOUS CHARGES

LABOR HRS. RATE AMOUNT

*37.33 TRENCH
2451.95 GENERAL*

| |
|-----------------|
| WORK ORDERED BY |
| DATE ORDERED |
| DATE COMPLETED |

| | |
|---------------------|--|
| TOTAL LABOR | |
| TOTAL MATERIALS | |
| TOTAL MISCELLANEOUS | |
| SUBTOTAL | |
| TAX | |
| GRAND TOTAL | |

CUSTOMER APPROVAL
SIGNATURE

AUTHORIZED SIGNATURE

R. W. [Signature]
(Tishman Const. as agent
for the City of Lawrence)

[Quantity Verification Only] JOB INVOICE